

**ADDENDUM #1**

This Addendum hereby forms part of the RFP. The purpose of this Addendum is to provide responses to questions received.

City's answers are in red.

Questions

1. **MMCD** specs are as follows. Are we following these specs:  
42 mm top , mid and bottom rails  
60 mm line posts  
73 mm corner posts  
89 mm gate posts  
All pipe ASTM heavy wall schedule 40 galvanized (then powder coated black).  
Spec on tie spacing: **what is the spacing of the ties?**

The fence is to be a design build component of the work, as detailed in the Contract Documents. The Contractor and the fencing supplier shall determine the appropriate tie spacing as part of the shop drawing process, to be reviewed and approved by the Contract Administrator.